

ERRATUM ONE

RFQ Number: 6750/28/08/2026 – Request for Quotation for the upgrade of power supply for water jet cutting machine in Building 45 at CSIR Scientia Campus

On 12 August 2026, the Council for Scientific and Industrial Research (CSIR) invited suitably qualified and experienced service providers to submit quotations for the above-mentioned Request for Quotation (RFQ).

The original RFQ document indicated the following:

- Line item 2– 3m*200mm*50mm wire mesh cable tray, Unit of measure: **M.**
- Line Item 8 – Scaffolding hire, Unit of measure: **Lumpsum.**
- Line Item 10 – Rubble removal and disposal of all debris to municipal approved site
- Closing date: **28 August 2026 at 16:30.**

Please note the following changes to the tender documents:

- Line item 2– 3m*200mm*50mm wire mesh cable tray, Unit of measure: **Each**
- Line Item 8 – Scaffolding hire, Unit of measure: **2 days**
- Line Item 10 – Rubble removal and disposal of all debris to municipal approved site **if applicable**
- **Added line item 12:** Functionally inspection and testing of 70mm² armoured cable from approximately 500m roll for a 40m run that needs to be installed on cable tray.
- The **revised closing date and time** for this tender is **04 September 2026 at 16:30.**

All other terms of the RFQ document remain unchanged.

The CSIR wishes to encourage you to submit a response to this tender and do apologise for any inconvenience caused as a result of this erratum.

Enquiries may be directed to tender@csir.co.za (Please use RFP number as subject reference).

Revised Annexure B
Bill of Quantities

Item no	Description	QTY	Unit of Measure	Unit Price	Total price (VAT exclusive)
1	Earth conductor/cable	40	M		
2	3m*200mm*50mm wire mesh cable tray	14	Each		
3	Moulded case 150A circuit breakers (MCCB)	1	Each		
4	600*400*200 Electrical enclosure	1	Each		
5	150 A 3 phase lockable Isolator	1	Each		
6	150A change over switch	1	Each		
7	Labour (decommissioning, installation, certification and commissioning)	1	Lumpsum		
8	Scaffolding hire	1	2 days		
9	Preliminaries and general	1	Lumpsum		
10	Rubble removal and disposal of all debris to municipal approved site if applicable	1	Lumpsum		
11	Safety File	1	Lumpsum		
12	Functionally inspection and testing of 70mm ² armoured cable from approximately 500m roll for a 40m run that needs to be installed on cable tray	40	M		
Sub-total					
Contingency @ 20%					
Sub-total + Contingency @ 20%					
15% VAT					
Total VAT Inc					