



REPUBLIC OF SOUTH AFRICA

CSIR

BILLS OF QUANTITIES
REVISION #01

RENOVATIONS ON VARIOUS CSIR BUILDINGS
BUILDING 42A

CSIR
MEIRING NAUDE ROAD
BRUMMERIA
PRETORIA
0184
OR
P.O BOX 395
PRETORIA
0001

QUANTITY SURVEYORS
QSOURCE QUANTITY SURVEYORS
33 OAKMONT STREET
SILVER LAKES
PRETORIA
0081
OR
P.O BOX 11680
SILVER LAKES
0051

CSIR
Renovations on various CSIR buildings
Revision #01

Item No		Quantity	Rate	Amount
	<p><u>BILL NO. 1</u></p> <p><u>PRELIMINARIES (PROVISIONAL)</u></p> <p>Note: Tenderers are advised to study the Model Preambles for Trades before pricing the Bill.</p> <p>Note: Unless otherwise stated herein, all items in the Bill shall be deemed to be a fixed price for the duration of this project</p> <p><u>BUILDING AGREEMENT AND PRELIMINARIES</u></p> <p>The JBCC Principal Building Agreement (Edition 6.2 - May 2018) prepared by the Joint Building Contracts Committee shall be the applicable building agreement, amended as hereinafter described</p> <p>The JBCC Principal Building Agreement contract data form an integral part of this agreement</p> <p>The JBCC General Preliminaries (May 2018) published by the Joint Building Contracts Committee for use with the JBCC Principal Building Agreement (Edition 6.2 - May 2018) shall be deemed to be incorporated in these bills of quantities, amended as hereinafter described</p> <p>The contractor is deemed to have referred to the abovementioned documents for the full intent and meaning of each clause</p> <p>The clauses in the abovementioned documents are hereinafter referred to by clause number and heading only</p> <p>Where any item is not relevant to this agreement such item is marked N/A signifying "not applicable"</p>			
	Carried Forward		R	
	Location [D] - Building 42 A Bill No. 1 PRELIMINARIES			

CSIR
Renovations on various CSIR buildings
Revision #01

<p style="text-align: center;">Brought Forward</p> <p>Where standard clauses or alternatives are not entirely applicable to this agreement such amendments, modifications, corrections or supplements as will apply are given under each relevant clause heading and such amendments, modifications, corrections or supplements shall take precedence notwithstanding anything to the contrary contained in the abovementioned documents</p> <p><u>PREAMBLES FOR TRADES</u></p> <p>The General Preambles for Trades 2017 published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>Supplementary preambles and / or specifications are incorporated in these bills of quantities to satisfy the requirements of this project. Such supplementary preambles and / or specifications shall take precedence over the provisions of the General Preambles</p> <p>The contractor's prices for all items throughout these bills of quantities shall take account of and include where applicable for all of the obligations, requirements and specifications given in the General Preambles and in any supplementary preambles and / or specifications</p> <p><u>STRUCTURE OF THIS PRELIMINARIES BILL</u></p> <p>Section A : A recital of the headings of the individual clauses in the aforementioned JBCC Principal Building Agreement</p> <p>Section B : A recital of the headings of the individual clauses in the aforementioned JBCC General Preliminaries</p> <p>Section C : Any special clauses to meet the particular circumstances of the project</p>		R	
<p style="text-align: center;">Carried Forward</p> <p>Location [D] - Building 42 A Bill No. 1 PRELIMINARIES</p>		R	

CSIR
 Renovations on various CSIR buildings
 Revision #01

	<p style="text-align: right;">Brought Forward</p> <p><u>PRICING OF PRELIMINARIES</u></p> <p>Should the contractor select Option A in the contract data for the adjustment of preliminaries, the amounts entered against the relevant items in these preliminaries are to be divided into one or more of the three categories provided namely fixed (F), value related (V) and time related (T)</p> <p><u>SECTION A: PRINCIPAL BUILDING AGREEMENT</u></p> <p><u>Interpretation (A1-A7)</u></p> <p>4/1/1 Clause 1.0 - Definitions and interpretation</p> <p>Pricing of bills of quantities</p> <p>The contractor is to allow opposite each item for all costs in connection therewith. All prices to include, unless otherwise stated, for all materials, fabrication, conveyance and delivery, unloading, storing, unpacking, hoisting, labour, setting, fitting and fixing in position, cutting and waste (except where to be measured in accordance with the standard system of measurement), patterns, models and templates, plant, temporary works, returning of packaging, duties, taxes (other than Value Added Tax), imposts, establishment charges, overheads, profit and all other obligations arising out of this agreement. Value Added Tax (VAT) is to be separately stated on the summary page of these bills of quantities</p> <p>Items left unpriced will be deemed to be covered in prices against other items throughout these bills of quantities and no claim for any extras arising out of the contractor's omission to price any item will be entertained</p> <p>Prices for all construction equipment, temporary works, services and other items shall include for the supply, maintenance, operating cost and subsequent removal and making good as necessary</p> <p style="text-align: right;">Carried Forward</p> <p>Location [D] - Building 42 A Bill No. 1 PRELIMINARIES</p>		<p style="text-align: center;">R</p>	
			<p style="text-align: center;">R</p>	

CSIR
Renovations on various CSIR buildings
Revision #01

	<p style="text-align: right;">Brought Forward</p> <p>Abbreviated descriptions</p> <p>The items in these bills of quantities utilise abbreviated descriptions. It is the intention that the abbreviated descriptions be fully described when read with the applicable measuring system and the relevant preambles and/or specifications. However, should the full intent and meaning of any description not be clear, the contractor shall, before submission of his tender, call for a written directive from the principal agent, failing which it shall be assumed that the contractor has allowed in his pricing for materials and workmanship in terms of international best practice</p> <p>Legal status of contractor</p> <p>If the contractor constitutes a joint venture, consortium or other unincorporated grouping of two or more persons then:</p> <ol style="list-style-type: none"> 1. These persons are deemed to be jointly and severally liable to the employer for the performance of this agreement 2. These persons shall notify the employer of their leader who has assigned authority to bind the contractor and each of these persons 3. The contractor shall not alter its composition or legal status without the prior written consent of the employer <p>F:..... V:..... T:.....</p> <p>4/1/2 Clause 5.0 - Documents</p> <p>Value Added Tax</p> <p>Provision is made in the summary page of these bills of quantities for the inclusion of Value Added Tax (VAT)</p> <p style="text-align: right;">Carried Forward</p> <p>Location [D] - Building 42 A Bill No. 1 PRELIMINARIES</p>	Item	R	
			R	

CSIR
Renovations on various CSIR buildings
Revision #01

	Brought Forward		R
	<p>Priced document as specification</p> <p>Clause 5.4 is deemed to be deleted</p> <p>The principal agent shall decide which portion of the priced document may be used as a specification of materials and goods or methods, if any</p> <p>Electronic issue of drawings</p> <p>All drawings for this project will be issued electronically and the contractor shall be deemed to have received such drawings on the date that such drawings have been dispatched electronically [5.6]</p>		
4/1/3	<p>Clause 12.0 - Obligations of the parties</p> <p>Statutory and other notices</p> <p>The contractor shall submit and/or comply with all statutory and other notices that may be required by any local or other authority in order not to cause any delay to the commencement of the works by the contractor. The contractor shall pay all deposits or fees in this regard</p> <p>It is, however, specifically recorded that the employer shall be responsible for the timeous approval of building plans by any local or other authorities and the payment of any fees or charges related thereto</p>		
4/1/4	Clause 14.0 - Nominated subcontractors		
4/1/5	Clause 15.0 - Selected subcontractors		
4/1/6	<p>Clause 16.0 - Direct contractors</p> <p>Attendance on direct contractors</p> <p>In respect of direct contractors the contractor shall:</p> <ol style="list-style-type: none"> 1. Designate an area for the direct contractor to establish a temporary office and workshop and storage of equipment and materials 		
	Carried Forward		R
	<p>Location [D] - Building 42 A Bill No. 1 PRELIMINARIES</p>		

CSIR
Renovations on various CSIR buildings
Revision #01

	Brought Forward		R
	<p>2. Allow the use of personnel welfare facilities, where provided</p> <p>3. Provide water, lighting and single phase electric power to a position within 50m of the place where the direct contract work is to be carried out, other than fuel or power for commissioning of any installation</p> <p>4. Permit the direct contractor to use erected scaffolding, hoisting facilities, etc provided by the contractor, in common with others having the like right, while it remains erected on the site [16.1]</p>		
4/1/7	<p>Clause 17.0 - Contract instructions</p> <p>Site instructions</p> <p>Instructions issued on site are to be recorded in a site instruction book which is to be supplied and maintained on site by the contractor</p>		
4/1/8	Clause 18.0 - Interim completion	N/A	
4/1/9	Clause 20.0 - Completion in sections		
4/1/10	Clause 21.0 - Defects liability period and final completion		
4/1/11	<p>Clause 23.0 - Revision of the date for practical completion</p> <p>Substitution of materials and goods</p> <p>The removal or substitution of any materials and goods which do not conform to the specification or the contract drawings shall not constitute grounds for the extension of the construction period nor for the adjustment of the contract value [17.1.8; 23.1 & 2]</p>		
4/1/12	Clause 25.0 - Payment		
	Carried Forward		R
	<p>Location [D] - Building 42 A Bill No. 1 PRELIMINARIES</p>		

CSIR
Renovations on various CSIR buildings
Revision #01

	Brought Forward		R
	<p>Prices submitted</p> <p>Where prices are submitted by the contractor or subcontractor during the progress of the works in respect of contract instructions or in regard to a claim under the terms of this agreement and notwithstanding the fact that such prices may be used in an interim payment certificate, there is to be no presumption of acceptance. Should the principal agent wish to accept any such prices prior to the issue of the certificate of final completion, it shall be in writing</p>		
4/1/13	<p>Clause 26.0 - Adjustment of the contract value and final account</p>		
	<p>Cost of claims</p> <p>All costs incurred by the contractor in the preparation of claims shall be borne by the contractor. This provision shall not preclude an adjudicator or an arbitrator appointed in terms of this agreement [30.6 & 7] from making a determination on costs</p>		
	<p>Claims from subcontractors</p> <p>The contractor shall review, assess and adjudicate any claims received by him from any subcontractor and thereafter submit same to the principal agent with a recommendation in order to assist the principal agent in adjudicating the claim [26.6]</p>		
4/1/14	Clause 28.0 - Suspension by the contractor		
4/1/15	Clause 29.0 - Termination		
4/1/16	<u>Agreement</u>		
4/1/17	<u>Contract data</u>		
	<p>Tenderer's selections</p> <p>Before submission of his tender the contractor is to complete the tenderer's selections in the contract data</p>		
	Carried Forward		R
	<p>Location [D] - Building 42 A Bill No. 1 PRELIMINARIES</p>		

CSIR
Renovations on various CSIR buildings
Revision #01

	Brought Forward		R
4/1/18	Clause 2.2 - Provisional bills of quantities		
4/1/19	Clause 2.3 - Availability of construction information F:..... V:..... T:.....		
4/1/20	Clause 9.1 - Responsibility for prime cost amounts		
4/1/21	Clause 10.2 - Special attendance		
	<u>SECTION C: SPECIFIC PRELIMINARIES</u>		
4/1/22	Warranties for materials and workmanship Where warranties for materials and/or workmanship are called for, the contractor shall obtain a written warranty, addressed to the employer , from the entity supplying the materials and/or executing the work and shall deliver same to the principal agent on final completion of the contract The warranty shall state that workmanship, materials and installation are warranted for a specific period from the date of practical completion and that any defects that may arise during the specified period shall be made good at the expense of the entity supplying the materials and/or doing the work, upon written notice to do so		
4/1/23	Health and safety Without limiting the generality of the provisions of clause 2.0, the contractor's attention is drawn to the provisions of the Construction Regulations issued in terms of the Occupational Health and Safety Act, 1993 as amended. It is specifically stated that the employer shall prepare a documented health and safety specification for the works and that the employer shall ensure that the contractor has made provision for the cost of health and safety measures during the execution of the works . The contractor shall price opposite this item for compliance with the act and the regulations and the reasonable provisions of the aforementioned health and safety specification [2.1]		
	Carried Forward		R
	Location [D] - Building 42 A Bill No. 1 PRELIMINARIES		

CSIR
Renovations on various CSIR buildings
Revision #01

Brought Forward		R	
<u>SUMMARY OF CATEGORIES</u>			
Category : Fixed	R.....		
Category : Value	R.....		
Category : Time	R.....		
Carried Forward to Summary of Section No. 4			
Location [D] - Building 42 A Bill No. 1 PRELIMINARIES			
		R	

CSIR
Renovations on various CSIR buildings
Revision #01

Item No		Quantity	Rate	Amount
	<p><u>BILL NO. 2</u></p> <p><u>ALTERATIONS (PROVISIONAL)</u></p> <p>Note: Tenderers are advised to study the Model Preambles for Trades before pricing the Bill.</p> <p>Note: Unless otherwise stated herein, all items in the Bill shall be deemed to be a fixed price for the duration of this project</p> <p><u>View site</u></p> <p>The tenderers are required to familiarise themselves on site with the dimensions, material and work required in order to price each item correctly in this bill of quantities</p> <p>Before submitting his tender the tenderer shall visit the site and satisfy himself as to the nature and extent of the work to be done and the value of the materials salvageable from the alterations. No claim for any variations of the contract sum in respect of the nature and extent of the work or of inferior or damaged materials will be entertained</p> <p><u>General</u></p> <p>The contractor shall carry out the whole of the works with as little mess and noise as possible and with a minimum of disturbance to tenants in the building and to adjoining premises and their tenants. He shall provide proper protection and provide, erect and remove when directed, any temporary tarpaulins that may be necessary during the progress of the works, all to the satisfaction of the principal agent</p> <p>Doors, fanlights, windows, fittings, frames, linings, etc which are to remain the property of the employer shall be carefully taken out, temporarily stored, transported over a distance of approximately 10km to store and handed over to the employer</p>			
	Carried Forward			R
	<p>Location [D] - Building 42 A Bill No. 2 ALTERATIONS</p>			

CSIR
Renovations on various CSIR buildings
Revision #01

<p style="text-align: center;">Brought Forward</p> <p>Doors, fanlights, windows, fittings, frames, linings, etc which are to be reused shall be thoroughly overhauled before refixing including taking off, easing and re-hanging, cramping up, re-wedging as required and making good cramps, dowels, etc, and oiling, adjusting and repairing ironmongery as necessary, replacing any glass damaged in removal or subsequently and stopping up all nail and screw holes with tinted plastic wood to match timber, unless otherwise described. Re-painting or re-varnishing is given separately</p> <p>Prices for taking out of doors, windows, etc shall include for removal of all beads, architraves, ironmongery, etc</p> <p>Prices for taking out and removing doors and frames shall include for removing door stops, cabin hooks, etc</p> <p>With regard to building up of openings in existing walls, cement screeds and pavings, granolithic, tops of walls, etc, shall be levelled and prepared for raising of brickwork</p> <p>Making good of finishes shall include making good of the brick and concrete surfaces onto which the new finishes are applied, where necessary</p> <p>The contractor will be required to take all dimensions affecting the existing buildings on the site and he will be held solely responsible for the accuracy of all such dimensions where used in the manufacture of new items (doors, windows, fittings, etc)</p> <p><u>Credit for old materials</u></p> <p>Provision is made in the final summary to quote for the value of old materials and measured elsewhere (Section: Removal of Existing Work refers)</p> <p><u>REMOVAL OF EXISTING WORK</u></p>		R	
<p style="text-align: center;">Carried Forward</p> <p>Location [D] - Building 42 A Bill No. 2 ALTERATIONS</p>		R	

CSIR
Renovations on various CSIR buildings
Revision #01

Brought Forward			R
	<u>Taking down and removing roofs, floors, panelling, ceilings, partitions, etc</u>		
4/2/1	Mineral fibre acoustic ceiling panels, size 1 200mm x 600mm from suspension grid in patches	m2	4
	<u>Taking out and removing sundry joinery work, fittings, etc</u>		
4/2/2	Whiteboards size 3 500mm x 1 400mm from brick walls including making good	No	1
	<u>Taking up and removing wood floor coverings, vinyl floor coverings, carpets, etc and preparing screeds for new floor coverings</u>		
4/2/3	300mm x 300mm Vinyl tiles from floors	m2	121
4/2/4	Loop pile wall to wall carpeting from floors	m2	69
	<u>Taking out and removing ironmongery to be refurbished or replaced to match existing or with similar approved (measured elsewhere)</u>		
4/2/5	Door stops from doors	No	49
4/2/6	Door handles from doors	No	1
4/2/7	Vertical blinds including railings and opening gear from brick walls including making good	m2	130
	<u>Taking out and removing steel security gates</u>		
4/2/8	"Trellidor" security gate with and including all ironmongery, overall size 2,2m x 2,5m from brick wall including making good	No	1
	<u>Hacking up / off and removing ceramic tiles including removing mortar bed or adhesive from concrete or brickwork and preparing surfaces for new screed, plaster, tile finish, etc</u>		
4/2/9	200mm x 200mm Tiles from walls in patches including making good	m2	0.2
Carried Forward			R
Location [D] - Building 42 A Bill No. 2 ALTERATIONS			

CSIR
Renovations on various CSIR buildings
Revision #01

Brought Forward			R
<u>Taking out / off and removing electrical work</u>			
4/2/10	Power skirting covering from power skirting bodies including making good to receive new	m	90
<u>Taking out / off and removing mechanical work</u>			
4/2/11	Air conditioning overflow pipes from walls and windows including making good	m	12
4/2/12	Air conditioning units from brick walls including making good	No	3
4/2/13	Fans from concrete ceilings including making good	No	6
<u>GENERAL MAINTENANCE</u>			
<u>Cleaning floor carpets</u>			
4/2/14	Loop pile wall to wall carpeting to floors	m2	336
<u>Investigating and repairing of possible mould damage</u>			
4/2/15	Mould damage to floors	m2	36
<u>Cleaning bathrooms</u>			
4/2/16	Deep cleaning of bathrooms including 2 toilets, 1 wash hand basins, etc with a total floor area of 13,34m2	No	1
<u>Testing and servicing air-conditioning unit</u>			
4/2/17	Air-conditioning split unit	No	1
<u>Replacing air-conditioner remote control</u>			
4/2/18	Air-conditioner remote, PC sum R300,00 each excluding VAT delivered to site	No	2
<u>Cleaning windows</u>			
4/2/19	Cleaning interior glass panes with soap and water solution	m2	132
Carried Forward			R
Location [D] - Building 42 A Bill No. 2 ALTERATIONS			

CSIR
Renovations on various CSIR buildings
Revision #01

		Brought Forward		R
4/2/20	Cleaning exterior glass panes with soap and water solution	m2	132	
Carried Forward to Summary of Section No. 4				R
Location [D] - Building 42 A				
Bill No. 2				
ALTERATIONS				

CSIR
Renovations on various CSIR buildings
Revision #01

Item No		Quantity	Rate	Amount
	<p><u>BILL NO 3</u></p> <p><u>CEILINGS, PARTITIONS AND ACCESS FLOORING (PROVISIONAL)</u></p> <p>Note: Tenderers are advised to study the Model Preambles for Trades before pricing the Bill.</p> <p>Note: Unless otherwise stated herein, all items in the Bill shall be deemed to be a fixed price for the duration of this project</p> <p><u>View site</u></p> <p>The tenderers are required to familiarise themselves on site with the dimensions, material and work required in order to price each item correctly in this bill of quantities</p> <p><u>Fixing</u></p> <p>Items described as "nailed" shall be deemed to be fixed with hardened steel nails or pins, or to be shot-pinned, to brickwork or concrete</p> <p>Items described as "plugged" shall be deemed to include screwing to fibre, plastic or metal plugs at not exceeding 500mm centres, and where described as "bolted", the bolts have been given elsewhere</p> <p><u>Ceilings</u></p> <p>Unless otherwise described ceilings shall be deemed to be horizontal</p> <p><u>Steel components</u></p> <p>All steel components for ceilings, partitions, etc are to be galvanised in accordance with SANS 121</p> <p><u>CEILING TIMBERS, BEADS, INSULATION, ETC</u></p>			
	<p>Carried Forward</p> <p>Location [D] - Building 42 A Bill No. 3 CEILINGS, PARTITIONS AND ACCESS FLOORING</p>		R	

CSIR
Renovations on various CSIR buildings
Revision #01

Brought Forward			R
<u>SUSPENDED CEILINGS</u>			
<u>1200 x 600 x 9mm "Gyproc" mineral fibre acoustic panels on exposed suspension grid system</u>			
4/3/1	Ceilings suspended not exceeding 1m below concrete soffits	m2	4
<u>PARTITIONS ETC</u>			
<u>DRYWALL PARTITIONS</u>			
<u>"Rhino-Drywall" partitions with 12,5mm thick "RhinoBoard" board cladding on both sides boards are to be butt jointed and finished with "Rhinotape" and "Readymix D" jointing compound all in accordance with the manufacturer's instructions</u>			
4/3/2	Partitions 2,94m high with bottom and top tracks plugged	m	15
4/3/3	Extra over partition 2,5m high for vertical end against plastered brick wall	No	2
4/3/4	Extra over partition 2,5m high for T-intersection	No	2
<u>Extra over "Rhino-Drywall" partitions for 40mm semi-solid flush doors with veneer on both sides and hardwood edge strips to vertical edges, hung to and including standard natural anodised aluminium door frame with one pair of 100mm nylon washered aluminium hinges to each hanging stile, including additional studding, trimming, etc. to partitions</u>			
4/3/5	Door 803 x 2 032mm high including "Euro brass" or similar lockset to match existing	No	2
<u>SKIRTING ETC.</u>			
<u>Aluminium skirting</u>			
4/3/6	<u>100mm High aluminium skirting</u>	m	26
Carried Forward to Summary of Section No. 4			R
Location [D] - Building 42 A			
Bill No. 3			
CEILINGS, PARTITIONS AND ACCESS FLOORING			

CSIR
Renovations on various CSIR buildings
Revision #01

Item No		Quantity	Rate	Amount
	<p><u>BILL NO 4</u></p> <p><u>FLOOR COVERINGS, WALL LININGS, ETC (PROVISIONAL)</u></p> <p>Note: Tenderers are advised to study the Model Preambles for Trades before pricing the Bill.</p> <p>Note: Unless otherwise stated herein, all items in the Bill shall be deemed to be a fixed price for the duration of this project</p> <p><u>View site</u></p> <p>The tenderers are required to familiarise themselves on site with the dimensions, material and work required in order to price each item correctly in this bill of quantities</p> <p><u>Fixing</u></p> <p>Floor coverings, wall linings, etc shall, where applicable, be fixed with adhesive as recommended by the manufacturers of the flooring, linings, etc</p> <p><u>FLOOR COVERINGS</u></p> <p><u>300mm x 300mm x 5mm Approved semi flexible vinyl tiles</u></p>			
4/4/1	On floors	m2	121	
	<p><u>500 x500mm "Belgotex Battleship" tufted multi scroll loop pile fibre stainproof SDX carpet tiles</u></p>			
4/4/2	On floors	m2	69	
	<p><u>SKIRTINGS, NOSINGS, ETC</u></p>			
	Carried Forward			R
	<p>Location [D] - Building 42 A Bill No. 4 FLOOR COVERINGS, WALL LININGS, ETC</p>			

CSIR
Renovations on various CSIR buildings
Revision #01

		Brought Forward		R
	<u>Vinyl skirtings, nosings, etc</u>			
4/4/3	100mm Approved semi flexible vinyl skirtings	m	34	
Carried Forward to Summary of Section No. 4				
Location [D] - Building 42 A				R
Bill No. 4				
FLOOR COVERINGS, WALL LININGS, ETC				

CSIR
Renovations on various CSIR buildings
Revision #01

Item No		Quantity	Rate	Amount
	<p><u>BILL NO 5</u></p> <p><u>IRONMONGERY (PROVISIONAL)</u></p> <p>Note: Tenderers are advised to study the Model Preambles for Trades before pricing the Bill.</p> <p>Note: Unless otherwise stated herein, all items in the Bill shall be deemed to be a fixed price for the duration of this project</p> <p><u>View site</u></p> <p>The tenderers are required to familiarise themselves on site with the dimensions, material and work required in order to price each item correctly in this bill of quantities</p> <p><u>Proprietary items</u></p> <p>Where applicable the manufacturers' names or product catalogue titles are given in sub-headings preceding the items</p> <p>Prices are to be based on the specific products / articles specified. If tenderers wish to offer alternative products / articles for certain items, these items are to be clearly marked and the alternative specification given with supporting brochures etc clarifying the features of the products / articles offered</p> <p>On request returnable samples are to be provided to the principal agent for consideration</p> <p><u>HANDLES</u></p>			
4/5/1	"Euro brass" or similar chrome plated door handle to match existing	No	1	
	<p style="text-align: right;">Carried Forward</p> <p>Location [D] - Building 42 A Bill No. 5 IRONMONGERY</p>		R	

CSIR
Renovations on various CSIR buildings
Revision #01

Brought Forward			R
<u>SUNDRIES</u>			
4/5/2	"Dortello" or similar approved floor mounted magnetic door stops fixed to concrete floors	No	49
<u>PHOTOLUMINESCENT SIGNS</u>			
<u>Wall mounted photoluminescent statutory signs in 150 x 150mm modules</u>			
4/5/3	300 x 150mm Sign with EXIT sign (Type Fire Exit)	No	2
<u>DRAPES, BLINDS, ETC</u>			
<u>Vertical blinds</u>			
4/5/4	"Aluvert" fabric vertical blinds size 3 550mm x 1 400mm high in the colour Kent Grey 11 with 90mm wide vanes, manual controls, left / right hand stacking head and bottom rails, blinds to be fitted inside reveal / or fixed face	No	19
4/5/5	"Aluvert" fabric vertical blinds size 3 500mm x 1 000mm high in the colour Kent Grey 11 with 90mm wide vanes, manual controls, left / right hand stacking head and bottom rails, blinds to be fitted inside reveal / or fixed face	No	3
4/5/6	"Aluvert" fabric vertical blinds size 2 300mm x 1 400mm high in the colour Kent Grey 11 with 90mm wide vanes, manual controls, left / right hand stacking head and bottom rails, blinds to be fitted inside reveal / or fixed face	No	1
4/5/7	"Aluvert" fabric vertical blinds size 1 100mm x 1 400mm high in the colour Kent Grey 11 with 90mm wide vanes, manual controls, left / right hand stacking head and bottom rails, blinds to be fitted inside reveal / or fixed face	No	5
Carried Forward			R
Location [D] - Building 42 A Bill No. 5 IRONMONGERY			

CSIR
Renovations on various CSIR buildings
Revision #01

Brought Forward		R
4/5/8	<p>"Aluvert" fabric vertical blinds size 600mm x 600mm high in the colour Kent Grey 11 with 90mm wide vanes, manual controls, left / right hand stacking head and bottom rails, blinds to be fitted inside reveal / or fixed face</p> <p style="text-align: right;">No</p>	2
<u>Horizontal blinds</u>		
4/5/9	<p>"Aluvert" Basswood horizontal blinds size 2 300mm x 1 400mm high in the colour white wash with manual controls fitted inside reveal / or fixed face</p> <p style="text-align: right;">No</p>	1
Carried Forward to Summary of Section No. 4		
Location [D] - Building 42 A		R
Bill No. 5		
IRONMONGERY		

CSIR
Renovations on various CSIR buildings
Revision #01

Item No		Quantity	Rate	Amount
	<p><u>BILL NO 6</u></p> <p><u>TILING (PROVISIONAL)</u></p> <p>Note: Tenderers are advised to study the Model Preambles for Trades before pricing the Bill.</p> <p>Note: Unless otherwise stated herein, all items in the Bill shall be deemed to be a fixed price for the duration of this project</p> <p><u>View site</u></p> <p>The tenderers are required to familiarise themselves on site with the dimensions, material and work required in order to price each item correctly in this bill of quantities</p> <p><u>Patterns</u></p> <p>Unless otherwise described, tiles shall be laid with continuous joints in both directions</p> <p><u>Fixing</u></p> <p>Unless described as "fixed with adhesive to plaster (plaster elsewhere)" descriptions of tiling on brick or concrete walls, columns, etc shall be deemed to include 1:4 cement plaster backing and descriptions of tiling on concrete floors etc shall be deemed to include 1:3 plaster bedding</p> <p>Tiling described as "fixed with adhesive on power floated concrete" shall be deemed to include for approved tiling key-coat</p> <p>Ceramic, porcelain, marble and granite tiles are to be fixed and grouted with suitable adhesives and grouts as recommended by the manufacturer of the tiles</p> <p><u>WALL TILING</u></p>			
	Carried Forward			R
	<p>Location [D] - Building 42 A Bill No. 6 TILING</p>			

CSIR
Renovations on various CSIR buildings
Revision #01

Brought Forward			R
4/6/1	<u>200mm x 200mm x 5mm White glazed ceramic tiles on brickwork including cement plaster backing to match existing</u> On walls in patches	m2	0.2
<u>FLOOR TILING</u>			
4/6/2	<u>600mm x 600m Full bodied double presses porcelain non-slip tiles in a shade of grey (to be approved) fixed with adhesive mixed with bonding liquid to screed and flush pointed with "Dove grey" grout</u> On floors and landings	m2	12
Carried Forward to Summary of Section No. 4			R
Location [D] - Building 42 A Bill No. 6 TILING			

CSIR
Renovations on various CSIR buildings
Revision #01

Item No		Quantity	Rate	Amount
	<p><u>BILL NO 7</u></p> <p><u>ELECTRICAL WORK (PROVISIONAL)</u></p> <p>Note: Tenderers are advised to study the Model Preambles for Trades before pricing the Bill.</p> <p>Note: Unless otherwise stated herein, all items in the Bill shall be deemed to be a fixed price for the duration of this project</p> <p><u>View site</u></p> <p>The tenderers are required to familiarise themselves on site with the dimensions, material and work required in order to price each item correctly in this bill of quantities</p> <p><u>Distribution boards etc</u></p> <p>Rates for distribution boards etc are to include for busbars, jumpers, neutral bars, internal wiring and connections, circuit identification markers, control gear labels, circuit legend cards and working drawings</p> <p><u>Switches, socket outlets, etc</u></p> <p>Rates for switches, socket outlets, etc are to include for screwing to outlet boxes, connecting up and cover plates</p> <p><u>Light fittings</u></p> <p>Rates for light fittings are to include for hanging, fixing and connecting and for lamp holders and fluorescent tubes and lamps of the type and wattage described</p> <p><u>GENERAL LIGHTING AND POWER</u></p>			
	<p style="text-align: right;">Carried Forward</p> <p>Location [D] - Building 42 A Bill No. 7 ELECTRICAL WORK</p>		R	

CSIR
Renovations on various CSIR buildings
Revision #01

Brought Forward			R
<u>POWER SKIRTINGS</u>			
4/7/1	"Cabstrut N8/801 fixed splice" power skirting powder coated cover	m	90
<u>Extra over for</u>			
4/7/2	End clip against wall (Provisional)	No	58
<u>LIGHT SWITCHES, SOCKET OUTLETS, ETC</u>			
4/7/3	16A Flush mounted one lever one-way switch unit complete with cover plate to match existing	No	2
<u>REPLACING OF LUMINARIES</u>			
4/7/4	Light bulb / tube in existing fittings to match existing	No	22
4/7/5	Florescent light covers size 1 200mm x 600mm to match existing	No	1
Carried Forward to Summary of Section No. 4			R
Location [D] - Building 42 A			
Bill No. 7			
ELECTRICAL WORK			

CSIR
Renovations on various CSIR buildings
Revision #01

Item No		Quantity	Rate	Amount
	<u>BILL NO 8</u>			
	<u>MECHANICAL WORK (PROVISIONAL)</u>			
	Note: Tenderers are advised to study the Model Preambles for Trades before pricing the Bill.			
	Note: Unless otherwise stated herein, all items in the Bill shall be deemed to be a fixed price for the duration of this project			
	<u>View site</u>			
	The tenderers are required to familiarise themselves on site with the dimensions, material and work required in order to price each item correctly in this bill of quantities			
	<u>AIR CONDITIONING INSTALLATION</u>			
	<u>"SPLIT TYPE" UNITS</u>			
4/8/1	"Samsung" or similar approved 12 000 BTU Inverter type mid wall unit with condensing unit mounted on external wall with approved brackets at a minimum of 600mm AFL all according to CSIR HVAC specifications (pipes and trunking measured elsewhere)	No	1	
4/8/2	"Samsung" or similar approved 18 000 BTU Inverter type mid wall unit with condensing unit mounted on external wall with approved brackets at a minimum of 600mm AFL all according to CSIR HVAC specifications (pipes and trunking measured elsewhere)	No	2	
	<u>CONDENSER WATER PIPEWORK ETC</u>			
	<u>Blue PVC air conditioning condensate drain pipes</u>			
4/8/3	25mm Pipes fitted through 6mm PVC sheet and glass panes (fitting and sealing to panes measured elsewhere) Provisional	m	19	
	Carried Forward			R
	Location [D] - Building 42 A Bill No. 8 MECHANICAL WORK			

CSIR
Renovations on various CSIR buildings
Revision #01

Brought Forward			R
4/8/4	25mm Pipes fitted through walls / ceilings / concrete slabs etc. including making good, sealing and making waterproof around pipe (Provisional)	m	20
	<u>Copper air conditioning refrigerant pipes</u>		
4/8/5	12mm Pipes fitted through walls / ceilings / concrete slabs etc. including making good of openings (Provisional)	m	19
	<u>PVC trunking</u>		
4/8/6	PVC trucking for 25mm PVC pipes fixed to walls / ceilings (Provisional)	m	19
	<u>Galvanised trunking</u>		
4/8/7	Galvanised trucking for 12mm copper pipes fixed to walls / ceilings (Provisional)	m	19
	<u>TESTING</u>		
	<u>Testing of air conditioning units</u>		
4/8/8	Vacuum and pressure testing of 12 000 BTU Inverter type mid wall unit	No	1
4/8/9	Vacuum and pressure testing of 18 000 BTU Inverter type mid wall unit with condensing unit	No	2
Carried Forward to Summary of Section No. 4			R
Location [D] - Building 42 A			
Bill No. 8			
MECHANICAL WORK			

CSIR
Renovations on various CSIR buildings
Revision #01

Item No		Quantity	Rate	Amount
	<p><u>BILL NO 9</u></p> <p><u>PAINTWORK (PROVISIONAL)</u></p> <p>Note: Tenderers are advised to study the Model Preambles for Trades before pricing the Bill.</p> <p>Note: Unless otherwise stated herein, all items in the Bill shall be deemed to be a fixed price for the duration of this project</p> <p><u>View site</u></p> <p>The tenderers are required to familiarise themselves on site with the dimensions, material and work required in order to price each item correctly in this bill of quantities</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>PREPARATORY WORK TO EXISTING WORK</u></p> <p><u>Previously painted plastered surfaces</u></p> <p>Surfaces shall be thoroughly washed down and allowed to dry completely before any paint is applied. Blistered or peeling paint shall be completely removed and screws shall be removed, cracks or screw holes shall be opened, filled with a suitable filler and finished smooth.</p> <p><u>Previously painted metal surfaces</u></p> <p>Surfaces shall be thoroughly rubbed and cleaned down. Blistered or peeling paint shall be completely removed down to bare metal</p>			
	Carried Forward			R
	Location [D] - Building 42 A Bill No. 9 PAINTWORK			

CSIR
Renovations on various CSIR buildings
Revision #01

Brought Forward			R
	<p><u>Previously painted wood surfaces</u></p> <p>Surfaces shall be thoroughly cleaned down. Blistered or peeling paint shall be completely removed and cracks and crevices shall be primed, filled with suitable filler and finished smooth</p> <p><u>ON INTERNAL GYPSUM PLASTER SURFACES</u></p> <p><u>One coat alkali resistant primer and two coats superior quality acrylic emulsion paint for interior and exterior use</u></p>		
4/9/1	Walls	m2	44
	<p><u>ON BAGGED BRICKWORK OR CONCRETE SURFACES</u></p> <p><u>Two coats superior quality acrylic emulsion paint for interior and exterior use</u></p>		
4/9/2	Ceilings and beams ("White" colour group)	m2	474
	<p><u>ON QUARRY TILE SURFACES</u></p> <p><u>Two coats acrylic Emulsion brick dressing</u></p>		
4/9/3	Brick skirtings	m	354
	<p><u>ON INTERNAL FLOATED PLASTER SURFACES</u></p> <p><u>Two coats superior quality acrylic emulsion paint for interior and exterior use - Plascon Cashmere Amazon Mist Y5-E2-3 or similar approved</u></p>		
4/9/4	Walls	m2	943
	<p><u>Two coats superior quality acrylic emulsion paint for interior and exterior use - Plascon Pantone 109 or similar approved (Provisional)</u></p>		
4/9/5	Walls	m2	30
	Carried Forward		R
	<p>Location [D] - Building 42 A Bill No. 9 PAINTWORK</p>		

CSIR
Renovations on various CSIR buildings
Revision #01

Brought Forward			R
	<u>Two coats superior quality acrylic emulsion paint for interior and exterior use - Plascon Pantone 376 or similar approved (Provisional)</u>		
4/9/6	Walls	m2	322
	<u>Two coats superior quality acrylic emulsion paint for interior and exterior use - Plascon Pantone 172 or similar approved (Provisional)</u>		
4/9/7	Walls	m2	20
	<u>ON METAL SURFACES</u>		
	<u>Spot priming bare metal surfaces, one coat alkyd based universal undercoat and two coats superior quality universal enamel paint</u>		
4/9/8	Door frames	m2	67
4/9/9	Floor cupboards	m2	15
4/9/10	Double stacked power skirtings	m	90
	<u>ON WOOD SURFACES</u>		
	<u>Two coats superior quality acrylic emulsion paint for interior and exterior use</u>		
4/9/11	Doors	m2	81
	Carried Forward to Summary of Section No. 4		
	Location [D] - Building 42 A		R
	Bill No. 9		
	PAINTWORK		

CSIR
Renovations on various CSIR buildings
Revision #01

Bill No	SECTION SUMMARY - Location [D] - Building 42 A	Page No	Amount
	Section No. 4		
	Location [D] - Building 42 A		
4/1	PRELIMINARIES	9	
4/2	ALTERATIONS	14	
4/3	CEILINGS, PARTITIONS AND ACCESS FLOORING	16	
4/4	FLOOR COVERINGS, WALL LININGS, ETC	18	
4/5	IRONMONGERY	21	
4/6	TILING	23	
4/7	ELECTRICAL WORK	25	
4/8	MECHANICAL WORK	27	
4/9	PAINTWORK	30	
	Carried to Final Summary		
	Location [D] - Building 42 A		R

CSIR
Renovations on various CSIR buildings
Revision #01

Section No	<u>FINAL SUMMARY</u>	Page No		Amount
1	Section 1	61		
	CONTINGENCY 10%		R	
	Sub Total		R	
	Tax 15%		R	
	Sub Total		R	
	LESS: Credit for old materials	Item		
	Carried to Form of Tender		R	