

08 February 2024

ERRATUM

(RFQ no: 6196.1/09/02/2024)

REQUEST FOR QUOTATION (RFQ) FOR THE CONSTRUCTION OF A RAINWATER HARVESTING SYSTEM, TO SUPPLY AND INSTALL AERATED TAPS AT THE CSIR SCIENTIA CAMPUS.

On Wednesday, 24 January 2024, the Council for Scientific and Industrial Research (CSIR) invited bidders to submit quotations for the above-mentioned RFQ. The original closing/submission date for the request is Friday, 09 February 2024.

The CSIR appreciates your interest in responding to the Request for Quotation.

1. Please note the following amendment in the advertised tender document:

- Design the plinth for the water tank of 10 000 Litre capacity with **19mm thick mesh and 40MPa concrete!** Dimension of the required plinth (L 4400mm W 1265mm H 300mm).
- Supply and install 15mm push type water taps with flow restrictor. **NB: SABS approved.**
- Supply and Install 450mm Flexi pipes. **NB: SABS approved.**

Annexure B, Price Schedules have been modified accordingly.

- The new closing date for submission of proposals is **16 Febraury 2024** at **16H30**.

Annexure B

Bill of Quantities

Item No	Description	Quantity	Unit Price (VAT Excl)	Total Price (VAT Excl)
1	Design of rainwater harvesting system	sum		
2	Design the plinth for the water tank of 10 000 Litre capacity with 19mm thick mesh and 40MPa concrete! <i>Dimension of the required plinth</i> (L 4400mm W 1265mm H 300mm)	sum		
3	Construct the plinth	sum		
4	Supply and install 10 kL tank with complete filters, 2,2 kW pump connections and chemical dosing for the rainwater harvesting unit including filtration	sum		
5	Excavations and backfill upon completion	25 m ³		
6	Supply and install 32 mm HDPE pipe with complete connections	204.5m		
7	Supply and install 22mm copper pipes from the system to the ablution block at building 37	100m		
8	Supply and install 10 valves with their fittings, coupling and accessories	sum		
9	Supply and install 15mm push type water taps with flow restrictor. NB: SABS approved	100		
10	Supply and Install 450mm Flexi pipes. NB: SABS approved	100		
11	Company, SHE file.	Sum		
Sub-Total (VAT Excl.)				
Contingency (10%)				
Sub - Total plus 10% Contingency				
VAT (15%)				
Grand Total				

All other terms of the RFQ document remain unchanged.

The CSIR wishes to encourage you to submit a response to this tender, and to apologise for any inconveniences caused as a result of this erratum.

Enquiries may be directed to tender@csir.co.za (Please use RFQ number as subject reference)